BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

No: EE/YNK/BBMP/E-PMT/19/2017-18 Dated: 17-02-2018

APPROVED TENDER SCHEDULE –'B'

Item No: 08

Name of Work:-Construction of anganavadi compound in ward no-01 of yelahanka Sub Division.

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri HARSHITH RAJ L R	
				Rate	Rate in Words
1	KSRB 2-2.1 : Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No.5/Item No. 2.3)KPWD S.R 2016-17	Cum	15.53	200.00	Rupees Two Hundred Only
2	KSRB 2-1.1 : Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications. specification. No. KBS 2.1 (a) / 2.3.1 (P.5/I.2.1)KPWD S.R 2016-17	Cum	47.25	166.00	Rupees One Hundred Sixty Six Only
3	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregate /sand/kaner/ Moorum KSRRB M100-1 Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications MORTH -100/ Chapter 1 (Page No.133/ Item No 17.1)	Cum	62.78	100.00	Rupees One Hundred Only
4	KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification No.KBS 4.1, 4.2 (P.12/I.4.3)	Cum	1.73	5159.00	Rupees Five Thousand One Hundred Fifty Nine Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri HARSHITH RAJ L R	
				Rate	Rate in Words
5	KSRB 5.2.3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 (Page No. 23/ Item No. 5.6)	Cum	10.35	4438.00	Rupees Four Thousand Four Hundred Thirty Eight Only
6	KSRB 5.2.3 : Providing and constructing granite / trap / basalt size stone masonry in superstructure with cement mortar 1:4, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at 2m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 (Page No. 23/ Item No. 5.13)	Cum	4.66	5908.44	Rupees Five Thousand Nine Hundred Eight and Paise Forty Four Only
7	KSRRB M300-53: Construction of embankment with approved material gravel/murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement table 300-2 complete as per specifications. (which includes cost of gravel/murrum, watering charges & compaction by vibratory roller) MORTH specification No. 305, P No. 148/ Item No. 19.60	Cum	18.90	320.12	Rupees Three Hundred Twenty and Paise Twelve Only
8	KSRB 4-1.7 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs with 20mm and down size graded granite metal coarse aggregate @ 0.84cum and fine aggregate @ 0.56 cum machine mixed concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, specification. No. KBS 4.1,4.2.(P No. 13 / Item No.4.7)	Sqm	1.04	5598.92	Rupees Five Thousand Five Hundred Ninety Eight and Paise Ninety Two Only
9	Providing and fixing M.S. Grill Over existing compound wall as per using 16mm x 16mm M.S square rod at 150mm c/c spacing and 6mmx40mm M.S flats at horizontal and 6mmx12mm M.S flat for ornamental design and providing shop edge design at the vertex of every vertical rods, including welding, grinding, wherever necessary.all the steel surface should be thoroughly cleaned free of rust and painted with anti corrosive paint (shop paint) etc.,complete.the work includes cost all materials, labour charges for all items of work, hire charges for welding cutting and grinding equipment, and electricity charges, etc., (Page No. 42/ Item No. 7.36)	Sqm	40.25	5537.44	Rupees Five Thousand Five Hundred Thirty Seven and Paise Forty Four Only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri HARSHITH RAJ L R	
				Rate	Rate in Words
10	Providing and fixing for flooring 20mm thick gang saw water cut sadarhalli grey granite in CM 1:4 proportion, cut to required shape pattern with paper joints finished with cement mortar using white cement colour pigment to match colour of slab making through jointing with sealent, grooves in joints including cost of all materials mortar and labour etc.,complete as per specifications -do- minimum width of 1200mm (Page No.109 / Item No.14.61.1)	Sqm	20.70	2105.16	Rupees Two Thousand One Hundred Five and Paise Sixteen Only
11	KSRB 14.6-2 : Providing and laying heavy duty cobble stones 60 mm thick interlock pavers, using cement and course sand for manufacture of blocks of approved size, shape and colour with a minimum compressive strength of 281 kg per sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in between joints, final compaction of paver surface joints into its final level, including cost of materials, labour and HOM of machineries complete as per specifications. (P No. 101 / Item No. 14.6)	Sqm	63.00	966.72	Rupees Nine Hundred Sixty Six and Paise Seventy Two Only
12	Fabricating, Providing and erecting in position of Hot dip galvanised M.S ornamental Security grill gate using 75x12 mm MS flat for Alround frame work woth verticle at the centre support MS Square of 20x20 mm of diffrence heights as shown in the drawing are to be fixed at 16cms C/C for Square bars of full height and 8cms C/C for bottom rods provide ornamental CI designers at the bottom and CI arrowsa in the middle and top. the entire frame work is to be fixed by means of expansion bolts to the brick pillars with necessary drilling holes. the work includes providing two coats of Enamel Painting ove one coat of red lead ready mix primer coat etc complete cost of all labour, painting, erection charges using hoist pulley cranes etc as per specification and drawings (Page No.41/ Item No.7.32)	Kgs	81.00	153.70	Rupees One Hundred Fifty Three and Paise Seventy Only
13	KSRB 15-18.3 : Providing and applying to enamel metal paint two coat (excluding priming coat) on over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications. (P.No.121 Item No.15.74)	Sqm	85.90	90.10	Rupees Ninety and Paise Ten Only

Harshith Raj L.R
Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.